BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

NO:BBMP/EE/YNK.D/EPMT-02/2020-21 Dt:06-5-2020

APPROVED TENDER SCHEDULE –'B'

Item 8

Name of Work :- Providing and installation of CC camera in ward no 03 & 04 of yelahanka Satellite town sub division

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri RAGHAVENDRA Y B	
				Rate	Rate in Words
1	Supplying ,installation ,Commissioning and Testing CP PLUS 3 MP , 50 meters ip bullet camera,1/3" 3MP PS CMOS Image Sensor,Max 25fps@3MP, 25/30fps@1080P,H.264, H.264H, H.264B , MJPEG dual-codec encoding,DWDR, Day/Night(ICR), 3DNR, ROI, AWB, AGC, BLC, HLC,3.6mm fixed lens (6mm optional),IR Range of 50 Mtrs, IP67, SD Card, PoE,Mobile Software: iCMOB, gCMOB,CMS Software: KVMS Pro, vOptimus Pro inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	8.00	23257.00	TwentyThree Thousand Two Hundred FiftySeven Only
2	Supplying ,installation ,Commissioning and Testing CP PLUS 32 Ch. H.265 4K Network Video Recorder Up to 32 channel IP camera input H.265/H.264 dual codec decoding Up to 8Mp resolution preview and playback Max 200Mbps incoming bandwidth Support 4 SATA HDDs up to 24TB, 2 USB(1 USB3.0) HDMI / VGA simultaneous video output Support Multi-brand network cameras ONVIF Version 2.4 conformance Mobile Software: iCMOB, gCMOB inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	1.00	69154.00	SixtyNine Thousand One Hundred FiftyFour Only
3	Supplying ,installation ,Commissioning and Testing Netgear ReadyNAS 4-Bay Diskless Network Attached Storage for Personal Cloud by Netgear inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	1.00	269112.00	Two Lakh SixtyNine Thousand One Hundred Twelve Only
4	Providing and Supplying NAS hard disk drives 6 TB inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	1.00	25030.00	TwentyFive Thousand Thirty Only

	pplying ,installation ,Commissioning and sting D-Link 24-Port Gigabit Switch With 4 ombo SFP Ports inclusive of all taxes and nsportation charges as per the direction of Engineer in Charge	Nos	1.00	35998.00	ThirtyFive Thousand Nine Hundred NinetyEight Only
	Supplying ,installation ,Commissioning and Testing D-Link 8-Port Gigabit Switch With 2 Combo SFP Ports inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	1.00	28861.00	TwentyEight Thousand Eight Hundred SixtyOne Only
7	Providing and Supplying CAT6 OUT Door 305 mtr Cable Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	1.00	66381.00	SixtySix Thousand Three Hundred EightyOne Only
8	Providing and Fixing Media converter Giga Dlink inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	1.00	11754.00	Eleven Thousand Seven Hundred FiftyFour Only
9	Providing Cctv MS poles with camera fixing brackets, 5 to 6 mtr height Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	3.00	24663.00	TwentyFour Thousand Six Hundred SixtyThree Only
10	Providing and Fixing MS Boxes for Poles with rust proof powder coating Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	3.00	8921.00	Eight Thousand Nine Hundred TwentyOne Only
11	Providing and Fixing Electrical work for boxes for power supply, fixing PVC Boards with three pin socktes and switches with protection MCB and cabling to street light electrical poles as per the direction of Engineer in Charge	Nos	3.00	7871.00	Seven Thousand Eight Hundred SeventyOne Only
12	Providing Internet charges connecting CCTV with IP Based for one month	Nos	12.00	3148.00	Three Thousand One Hundred FourtyEight Only
13	Providing and Fixing SFP-LX-SM GIGA MODULE Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	2.00	6297.00	Six Thousand Two Hundred NinetySeven Only
14	Providing and Fixing Fibre Optic PATCH Chords Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	1.00	2309.00	Two Thousand Three Hundred Nine Only

	pplying ,installation ,Commissioning and esting UPS 2 KVA with two batteries Box nclusive of all taxes and transportation charges per the direction of Engineer in Charge	Nos	1.00	67588.00	SixtySeven Thousand Five Hundred EightyEight Only
	Erecting of pole .The pole shall be erected n cement concrete work(1:2:4) including earthwork excavation and refilling of planting depth of the pole to the ground level and the copping CC shall be upto 0.6m above ground level as per IS 2713-7.1 Erection of lightduty pole on footpath a) 7.5m as per IS 410 Sp 5 charges as per the direction of Engineer in Charge	Nos	3.00	6611.00	Six Thousand Six Hundred Eleven Only
17	Providing and Fixing HDMI Cables 10 Mtrs inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	3.00	6507.00	Six Thousand Five Hundred Seven Only
18	Supplying ,installation ,Commissioning and Testing Video Manager Application Software for Display and Management of Camera on Video Display Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	1.00	35158.00	ThirtyFive Thousand One Hundred FiftyEight Only
19	Supplying ,installation ,Commissioning and Testing Server rack 15u Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	1.00	36217.00	ThirtySix Thousand Two Hundred Seventeen Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.